



STAGE 1: 3 BUILDINGS COMPLETED FROM EXCAVATION TO LOCK-UP STAGE IN 11 MONTHS

ENOGGERA BARRACKS ENOGGERA, QLD

For this Project of the Month we see why AFS LOGICWALL was chosen for this large Defence Housing Development. The unique features of the wall system contribute to speed of construction and structural capacity, accompanied by reliable delivery service from AFS...

AFS were initially contacted by John Holland Group in the search of an ultra-fast and efficient structural walling system for the LIA Stage 1 - 3 within the Gallipoli Barracks Army base in Enoggera, QLD.

Conventional block work and other walling systems were investigated but AFS LOGICWALL was chosen due to its unique features including:

- Pre-fabricated 90 degree corner panels with inbuilt "L" reo bars providing the necessary bracing for the buildings
- Inherent steel stud framework contributing to the reinforcement
- Water-resistant durable fibre-cement face sheeting

The Builder's expectation of performance was further achieved by reliable deliveries to site by AFS' own Logistics arm, and fast, quality installation by dedicated installers.

AFS were given high commendation by the builder for their contribution to this project.

FACTS & FIGURES

STAGE 1 & 2

Units
360

Height
3 Levels, 7 Buildings

Quantity of AFS LOGICWALL
Approx. 13,500m²

Applications
AFS 162 Party Walls
AFS 162 Bracing Walls

WHAT OUR CLIENT SAYS...

"The AFS LOGICWALL system provided benefits in time and quality, allowing us to mitigate risk."

For more inspiring projects and testimonials [CLICK HERE](#) to visit our website